



Comments: Flashing a min. 200mm (8") high whenever possible and must be above flood level.

Spanning of vertical wall panel joints (i.e. Tilt up walls) with Term. bar is not acceptable. Bar must be broken with no greater than 6mm (1/4") gap, and fastened within 50mm (2") of each end.

Masonry surfaces must be fully cured (min. 28 days) to facilitate proper bonding.



**Mid-Parapet Termination
(Termination Bar)
Roofing System Detail**

Scale: Not to scale

Date: August, 2016

Detail No.: P-S-212